ADDENDUM NO. 1
TO
THE CONTRACT DOCUMENTS FOR FAIRVIEW AVENUE

EBBS CREEK CULVERT REPLACEMENT

BID OPENING: THURSDAY APRIL 14, 2016 – 11:00 A.M.

To All Plan Holders:

The following changes, additions and/or deletions are being made and are hereby a part of the Contract Documents for Fairview Avenue Ebbs Creek Culvert Replacement, as fully and completely as if same were fully set forth therein:

A. Project Specifications, Pg. 4

1. **ITEM NO. 17 – INSTALL 60" X 72" PRECAST CONCRETE BOX CULVERT**
   ADD the following after the first paragraph:
   The precast box culvert will be supplied by County Materials Corporation. The box will be supplied in 57 sections with a typical section 6' in length; with weight of 2520 lbs. /foot. The box sections are required to be tied at sections under the roadway and at the mitered bend (18 sections total). The supplier will provide external joint wrap, ties, and mastic sealant.

   The approved shop drawings can be obtained electronically by contacting Kyle Vandercar at 414-762-2222 ext. 136 or vandercar@smwi.org.

2. **ITEM NO.19 – Wood Railings**
   ADD the following after the first paragraph:
   Wood railings shall be installed on top of the end wall and wing walls on both end sections as shown on sheet C9.0. On the easterly (out fall) end, the railings shall extend parallel to the sidewalk from the head wall rail an additional 48 ft. (total length of 58 ft., plus wing wall rails).

This addendum is hereby made a part of the contract documents.

All bidders shall acknowledge receipt and acceptance of this Addendum No. 1 consisting of one (1) page, by signing in the space provided and submitting the signed addendum with the bid. Bids submitted without this addendum may be considered non-responsive. Dated this 13th day of April, 2016.

CITY OF SOUTH MILWAUKEE

Receipt acknowledged and conditions agreed to
this _____ day of _____

_____
Bidder

_____
By

_____
Kyle Vandercar, P.E.
City Engineer