

**ADDENDUM NO. 1
TO
THE CONTRACT DOCUMENTS FOR
SOUTH MILWAUKEE PUBLIC LIBRARY
VINYL FLOOR AND CARPET TILE INSTALLATION**

To All Plan Holders:

The following changes, additions and/or deletions are being made and are hereby a part of the Contract Documents for South Milwaukee Public Library Vinyl Floor and Carpet Tile Installation as fully and completely as if same were fully set forth therein:

- 1. Cantilever shelving floor anchors: The 7 ft. high shelving on the first floor (9 rows of 10 unit shelving) and 5 ½ ft. high shelving on the second floor (6 rows of 8 unit shelving) are anchored to the concrete floor. Contractor shall realign the shelving, plumb and anchor the shelving through the new carpet tile with Tap con or other appropriate anchor. The end sections and alternating sections shall be anchored with 4 anchors.**
- 2. Contractor should plan to disassemble the long rows of shelving into 4 units or less for moving to prevent damage.**
- 3. LVT-1 and LVT-2 shall be installed in a checkerboard pattern where identified in plans.**
- 4. Vinyl floor base shall be installed along the stair treads with top parallel to slope of the stairs, notched at each tread (similar to rear emergency stairwell, or as approved by the Library Director).**

This addendum is hereby made a part of the contract documents.


All bidders shall acknowledge receipt and acceptance of this Addendum No. 1 consisting of one (1) page, by signing in the space provided and submitting the signed addendum with the bid. Bids submitted without this addendum may be considered non-responsive. Dated this 31st day of January 2018.

Receipt acknowledged and conditions agreed to
this _____ day of _____

Bidder

By

CITY OF SOUTH MILWAUKEE



Kyle Vandercar, P.E.
City Engineer